

Price/Financial Bid**SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF IP BASED CCTV SURVEILLANCE SYSTEM
AT FDA BHAWAN, KOTLA ROAD, NEW DELHI-110 002**

S. No.	Description of Item	Qty.	Unit	Rate	Amount
1	Bullet Camera – Varifocal Motorized Lens Supply, Installation, Testing and Commissioning of 2 MP bullet Motorized Vari-focal lens camera with minimum or better parameters:	03	Nos.		
2	Dome Camera – Fixed Lens Supply, Installation, Testing and Commissioning of 2 MP Dome fixed lens camera with minimum or better parameters:	20	Nos.		
3	Dome Camera – Fixed Lens For Lift Supply, Installation, Testing and Commissioning of 2 MP Dome fixed lens camera with TX & RX minimum or better parameters:	02	Nos.		
4	Network Video Recorder Supply, Installation, Testing and Commissioning of 36 Channel Network video recorder with minimum or better parameters:	01	No.		
5	SURVEILLANCE HDD Supply, Installation, Testing and Commissioning of Surveillance HDD with minimum or better parameters: 6TB HDD	02	Nos.		
6	Layer 2 SWITCH Supply, Installation, Testing and Commissioning of 8 Port Switch with 2 SFP minimum or better parameters:	05	Nos.		
7	Layer 2 SWITCH Supply, Installation, Testing and Commissioning of 24 Port Switch with 2 SFP minimum or better parameters:	01	Nos.		
8	SFP MODULE / TRANSRECEIVER Single Mode	12	Nos.		
9	Professional Display Supply, Installation, Testing and Commissioning of 43” LED Display with minimum or better parameters:	02	No.		
9	Indoor Server Rack Supply, Installation, Testing and Commissioning of 6U Rack with minimum or better parameters:	05	Nos.		
10	Indoor Server Rack Supply, Installation, Testing and Commissioning of 22U Rack with minimum or better parameters:	01	Nos.		

11	Unarmoured CAT6 Cable Supply, Laying, Testing and Termination of CAT6 Cable with minimum or better parameters:	1230	RMtr		
12	Patch Cord Supply, Laying, Testing and Termination of CAT6 Patch Cord 1 MTR with minimum or better parameters:	50	Nos.		
13	Flexible Conduit Supply, Laying, Testing and Termination of Flexible for Indoor/Outdoor with all accessories on wall surface	50	RMtr		
14	LIU DRAWER TYPE FULLY LOADED Supply, Installation, Testing and Commissioning of 6 Fiber patch panel with minimum or better parameters As per Specifications	06	Nos.		
15	FIBER CABLE ARMoured 6 Core Fiber Cable Single Mode (As per Specification)	200	RMtr		
16	FIBER Patch Cord Supply, Laying, Testing and Termination of Fiber Patch Cord 1 Mtr with minimum or better parameters:	12	Nos.		
17	Supply, Laying & Fixing of 25 mm PVC Pipe (Medium)	1400	RMtr		
18	IO & Face Plate	50	Nos.		
19	Junction/Gang Box	25	Nos.		
20	2 KVA ONLINE UPS WITH MINIMUM 1 HOUR BACKUP WITH RACK & ACCESSORIES (With External 26AHx6 Nos Batteries) (ALL COMPLETE)	01	No.		
21	Supply, Installation, Testing & Splicing of fiber cable with accessories	66	Nos.		
	Total Amount				
	Add : Applicable GST				
	Grand Total Amount (in Rs.)				

*It may be noted that the rates for the above stated items be quoted as per tender specifications/make. Taxes/GST also to be clearly mentioned. No consideration/contention shall be allowed at later stage.

SIGNAUTRE OF THE BIDDER WITH STAMP